

DAV PUBLIC SCHOOL



SASARAM-ARA ROAD, SEMRA, BIKRAMGANJ, ROHTAS -802212 (BIHAR)


A Secondary English Medium CO-Educational School

(Affiliated to Central Board of Secondary Education, Delhi, Affiliation No.-330389, School Code-65390)

Mobile No.- 6202036332(O), E-mail – davbikramganj@yahoo.in, davbkj@gmail.com, Website : davbikramganj.com

निविदा सूचना

डी.ए.वी. पब्लिक स्कूल आरा-सासाराम सेमरा रोड, बिक्रमगंज विद्यालय के मुख्य गेट एवं प्रहरी कक्ष निर्माण हेतु पंजीकृत एवं विश्वसनीय व्यावसायिक संस्थाओं (Agency) से निविदा आमंत्रित है। इच्छुक संस्थान से अनुरोध है कि सीलबंद लिफाफे में अपना कोटेसन 15/11/2023 दिन - बुधवार तक प्रस्तुत करें। विशेष जानकारी विद्यालय के वेवसाइट- davbikramganj.com से प्राप्त की जा सकती है। कार्यालय का फोन नंबर- 6202036332.


प्राचार्य
04/11/2023

Principal
D.A.V. Public School
Bikramganj
Sasaram-Ara-Road
Semra (Rohtas)
AFF-No-330389

ABSTRACT OF COST FOR CONSTRUCTION OF MAIN GATE, GUARD ROOM, AND WAITING ROOM WITH TOILET AT
D A V BIKRAMGANJ, BIHAR

Ref no - DAV-HA-359

Date - 22.4.2023

Serial	SoR	Particulars	Quantity	Rate	Unit	Amount
1	2.8.1	Earth work in excavation in foundation trenches or drains(not exceeding 1.5 m in width or 10 sqm on plan) including dressing of sides and ramming of bottoms, lift upto 1.5 including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m.All Kinds of soil	85.0		Cu m	
2	2.28	Supplying and filling in plinth with Local sand including watering, ramming, consolidating and dressing complete	34.0		Cu m	
3	11.72	Providing designation 100A one brick flat soling joints filled with local sand complete	34.0		Sq m	
4	4.1.3	Providing PCC (1:2:4) with graded Stone chips of 20 mm nominal size excluding the cost of centring and shuttering all works in Foundation all complete	2.8		Cu m	
5	5.1.2	Providing and laying in position specified grade of reinforced cement concrete in foundation excluding the cost of centring, shuttering, finishing and reinforcement- 1:1:5:3(1 cement: 1.5 coarse sand:3 graded stone aggregate 20 mm nominal size)	3.4		Cu M	
6	5.2.2	Reinforced cement concrete work in wall (any thickness), including attached plasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts, etc. upt floor five level excluding cost of centring, shuttering, finishin and reinforcement. 1:1:5:3(1 cement: 1.5 coarse sand:3 graded stone aggregate 20mm nominal size)	9.0		Cu m	
7	5.3	R C C work in beams, suspended floors, roofs having slope upto 15, landings, balconiec, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases upto floor five level excludingthe cost of centring, shuttering, finishing and reinforcement with 1:2:4(1 cement:2 coarse sand:4 graded stone aggreagate 20 mm nominal size).	17.8		Cu m	

8	5.22	Reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete. Thermo-Mechanically Treated bars TMTC-500-	290.0	97.30	KG	28,217
9	5.9	Centring and shuttering including strutting, propping etc. and removal of form for.				
	5.9.1	Foundations, footings, bases of columns etc. for mass concrete.	26.3		Sq m	
	5.9.3	Suspended floors, roots, landings, balconies and access platform.	47.1		sq m	
	5.9.6	Columns, Pillars, Piers, Abutments, Posts and Struts	7.8		sq m	
	5.9.5	Lintels, beams, plinth bams, grids, bressumers and cantilevers.	2.5		sq m	
10	6.1.12/1	Fly ash Brick work with cement mortar (1:4) in Foundation & Plinth	18.0		Cu m	
11	13.11.4	12 mm (1:6) cement Plaster	115.0		Sq m	
12	11.38	Providing and laying Ceramic glazed floor tiles 300x300 mm (thickness to be specified by the manufacturer) of ist quality conforming to IS : 15622 of approved make in colours such shades except white , Ivory , Grey , Fume Red , Brown , laid on 20 mm thick Cement motar 1:4 (1 cement: 4 coarse sand) including pointing the joints with white cement and matching pigment etc., complete.	66.6		Sq m	
13	11.23.2.1	18 mm thick marble flooring over 20 mm base in cement mortar (1:4) including rubbing and polishing all complete	29.3		Sq m	
14	13.78.1	Providing one coat of cement primer of approved brand and manufacture on wall surface all complete	259.9		Sq m	
15	13.79.1	Providing water proof cement paint of approved brand and manufacture and of required shade to give and even shade three or more coat on new work all complete	259.9		Sq m	
16	13.93.1	Painting with synthetic enamel two or more coats over Wood and Steel Work	53.6		Sq m	
17	N A	Door	3.0		EACH	
18	N A	WINDOW	6.0		EACH	
19	N A	metallic letters, providing and installation along with Fan and light installation in guard room and fixing and connecting of display lights on entrance gate				
20	N A	Barriers	1.0		EACH	
21	10.32.2	Providing and fixing MS Gates @ 25 Kg per Sq m with a coat of approved steel Primer all complete	535.3		KG	
Total						